

Jadual Spesifikasi Pemasangan Infrastruktur Rangkaian Atlet Centre, Pejabat MACE dan Casa 4

Bil	Perkakasan	Perincian	Kuantiti (Unit)	Kos (RM)	Jumlah (RM)
A	Perkakasan				
1	Switch	24 port, POE+, 4 sfp 1g	3		
2	Uplink	UTP CAT 6 (From L1 Pavi to MACE)	1		
		UTP CAT 6 (From L1 Pavi to Atlet Center)	1		
3	LAN	UTP CAT 6 (From SW to Workstation)	28		
4	Access Point	IEEE802.11ax, Both 2.4 Ghz and 5GHz	3		
5	AP Uplink	UTP CAT 6 (From SW to AP)	3		
6	Switch Rack	15U perforated wall mount	1		
7	Switch Rack	24U perforated floor	1		
8	Patch Panel	CAT 6, 24 port	3		
9	Cable Management	Cable Management	3		
10	Patch Cord	CAT 6, 3 mtr	62		
11	Power Supply	Socket power 3 pin	2		
B	Perisian				
11	Cloud License	Access Point Controller (3 tahun)	3		
C	Perkhidmatan dan Pemasangan dan Sokongan				
12	Installation	Configuration, installation, testing & commissioning network	1		
13	Support	3 years Support	1		
Jumlah Keseluruhan (RM)					